


COMFORT STATION



CABIN

SITE PLAN
Scale: 1"=50'-0"



Legend

- Site Boundary
- Major Contour
- Minor Contour
- Easement
- 100' Shoreline Buffer
- Fence
- Existing 50' R.O.W.
- Landscape Buffer
- Beach
- 6' wide Cobblestone paved path
- 6' wide mulch/gravel path
- 3' wide mulch/gravel path
- Private access path
- Low Landscape or Bush
- Existing Coniferous Trees to remain
- Existing Deciduous Trees to remain
- Point of Interest, Community Fire pit with benches

SITE DATA:

| | |
|---|----|
| CABINS 14' wide x 34' long includes 6' front porch | 11 |
| ONSITE MANAGEMENT CABIN 14' wide x 34' long includes 6' front porch | 1 |
| TOTAL | 12 |

Total Lot Area= 6.9 Ac. Total Gross Floor Area:
 Open/Green Space Area= 6.63 Ac. Comfort Station = 1,200 S.F.
 Percentage of Open/Green Space= 96.08% Cabins (12) = 5,712 S.F.
 Carleton Villa = 15,000 S.F.
 Total = 21,912 S.F.

Note:
 1. Each unit shall have a picnic table, fire pit, grill and solar panel.

Zoning Law: Town of Cape Vincent
 Section 3.7 Islands District
 1. Intent:
 The Islands District consists of five islands within the boundaries of the Town of Cape Vincent. They include Grenadier, Little Grenadier, Fox, Carleton, and Linda Islands. Carleton and Grenadier Islands have historic areas of interest as confirmed by the New York State Office of Parks, Recreation, and Historic Preservation. As such, land use on or near any area of historic interest will be taken into consideration during the approval process. This district represents the most distinctive land-use zone within the Town. Residents of the Islands District have a unique property and living arrangement; one that is both unconventional and independent. Residents do not want or need elaborate infrastructure development. The land-use plan for this District is focused principally on encouraging quality residential development with some capacity for limited, controlled commercial development, for example, restaurant, hotel, bed and breakfast.

2. Lot Requirements:

| Table 7 | Area Minimum | Frontage Minimum | Setbacks Minimum | | | Height Maximum |
|--------------------|----------------|------------------|------------------|------|------|----------------|
| | | | Front | Side | Rear | |
| Permitted | Five (5) Acres | 300' | 200' | 50' | 50' | 35' |
| Special Use Permit | Five (5) Acres | 300' | 200' | 50' | 50' | 35' |

Section 7.12 Recreational Resorts:
 1. Intent
 In order to take maximum advantage of the unique characteristics of this area, a designation of Recreational Resorts is established for campgrounds and RV parks.
 2. The term Recreational Resort shall be construed to include all related functions normally associated with transient resorts, such as, but not limited to:

- a. Tent camping sites
- b. RV camping sites
- c. Seasonal motor home sites
- d. Cabins, motel units
- e. Bathhouse, restroom facilities
- f. Marinas
- g. On-site convenience stores
- h. On-site laundromat
- i. Swimming pools
- j. Swimming beaches
- k. On-site recreation such as golf
- l. Restaurant

3. All applicable local, county, and state regulations shall be followed.

NOTES
 Do not scale drawings. Request verification of dimensions as required.
 Drawings represented in these documents are for information purposes only and shall not be used for construction.

Copyright reserved. All parts of this drawing are the exclusive property of Nadi Design and Development Inc. and shall not be used or reproduced without their permission.

FOR INFORMATION ONLY.
NOT FOR CONSTRUCTION.

| No. | Date | Issue Notes |
|-----|------|-------------|
| | | |

| No. | Date | Revisions Notes |
|-----|------|-----------------|
| | | |

PROJECT TITLE: CARLETON VILLA
PROJECT ADDRESS: Carleton Island Rd. 1
 Tax Map Parcel No. 39.27-1-16 in Town of Cape Vincent
CLIENT: Carleton Villa, LLC.
 Applicant: Ron Clapp
 Address: 146 Centre Street, Cape Vincent, NY 13618

SUB-CONSULTANT:
SHEET TITLE: SITE PLAN

DRAWN BY: NS
REVIEWED BY: MS
DATE: 1/25/2024
PROJECT ID: 23-072

SCALE: AS NOTED
PAPER SIZE: 36"x24"
SHEET #: